SYMBOL LEGEND (IEC 60617 forms)

- Circuit breaker
- Circuit breaker, withdrawable
- Disconnector
- Switch-disconnector
- Fuse
- Earthing switch
- Current transformer (2 cores)
- Voltage transformer
- Surge arrester / SPD
- Busbar (weight per level)
- Transformer, 2 windings
- Earth
- G 3~ Generator, 3-phase
- Rectifier (ac/dc), inverter (dc/ac)
- Static bypass switch
- Battery
- Adjustable inductor (Petersen coil)
- Resistor
- Busbar trunking / busway
- Wh Energy meter (Wh)
- 51 Protection relay, device no.
- Optical arc sensor
- Interlock (mechanical / key)
- Protection / control signal
- Off-sheet connector

LINE CODE (black on white; no colour code)

130 kV conductor	20 kV conductor	0.4 / 0.69 kV conductor
130 kV busbar	20 kV busbar	0.4 / 0.69 kV busbar
UPS / critical busbar	protection / control	interlock

Voltage level is also stated on every busbar tag; genset and BESS circuits use the LV weight.

UPS COMPOUND SYMBOL (all sheets)

rectifier ac/dc (top), inverter dc/ac (bottom),
DC link with battery to the side;
drawn the same for IT UPS and mechanical UPS.

DRAWING LIST (Rev P2)

Drawing / sheet	Title
SLD-000	Legend, drawing list, notes
SLD-001 sh 1	130/20 kV substation
SLD-001 sh 2	20 kV main switchgear MSG-20
SLD-002 sh 1	Data hall DH-1: HV-DH1, blocks
SLD-002 sh 2	DH-1: UPS, busways, mechanical
SLD-003 sh 1	Power block A: T-A, G-A, MSB-A
SLD-003 sh 2	Power block A: UPS to rack
SLD-004	BESS plant 10 MW / 20 MWh

ABBREVIATIONS

ACB / VCB air / vacuum circuit breaker
ATS automatic transfer (open transition)
ARMS arc-reduction maintenance switch
BTS busbar trunking system
MSB / UOSB main / UPS output switchboard
SBS / MBB static / maintenance bypass
PCS / EMS power conversion / energy mgmt
ZSI zone-selective interlocking
LoM loss of mains (ROCOF / vector shift)
(A) assumed value

GENERAL NOTES

1. Concept drawings for a fictional campus; not for construction. Public standards, [ASSUMED] data.
2. Ratings per DB-001 Rev P2 and CALC-002/003/004.
3. Relay functions: IEEE C37.2 device numbers.
4. Minimum text 10 pt = 2.57 mm cap height at A3 (checked by scripts/check_drawings.py).

P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

Legend, drawing list, notes
Symbols to IEC 60617 · lettering to ISO 3098
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-000	**1 / 1**	**P2**