


### 4N/3 ALLOCATION

| Pair-group | Busways (block 1) | Busways (block 2) | IT load |
|---|---|---|---|
| AB | BW-A1, BW-A2 | BW-B1, BW-B2 | 0.83 MW |
| AC | BW-A3, BW-A4 | BW-C1, BW-C2 | 0.83 MW |
| AD | BW-A5, BW-A6 | BW-D1, BW-D2 | 0.83 MW |
| BC | BW-B3, BW-B4 | BW-C3, BW-C4 | 0.83 MW |
| BD | BW-B5, BW-B6 | BW-D3, BW-D4 | 0.83 MW |
| CD | BW-C5, BW-C6 | BW-D5, BW-D6 | 0.83 MW |

Each rack is dual-corded to the two blocks of one pair-group (2 busway runs per block).

### LOADING (CALC-002)

| Case | Block load | UPS | Busway |
|---|---|---|---|
| Normal | 1.25 MW | 63 % | 307 A |
| Loss of 1 block | 1.67 MW | 83 % | 614 A |
| DCIM limit | ≤ 1.67 MW | — | Ir 800 A |

### NOTES

1. UOSB 3 200 A, Icw 65 kA 1 s; SPD type 2.
2. Busway MCCB 800 A current-limiting, Icu ≥ 50 kA, tested conditional rating ≥ 40 kA (IEC 61439-6).
3. Busway 800 A, Icw 36 kA; tap-off 63 A MCCB Icu ≥ 36 kA; rack PDU SCCR ≥ 15 kA (CALC-003).
4. Battery per UPS module LFP 165 kWh (5 min).
5. Block A detail: SLD-003 sh 1–2.

| | | |
|---|---|---|
| **P2** | 2026-10-25 | CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text |
| **P1** | 2026-10-24 | First concept issue |

**Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3**
Portfolio D. Wu · public standards and [ASSUMED] data only

**Data hall DH-1 — sheet 2**
UPS, UOSB, busways to 4N/3 pair-groups; mechanical 2N
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

| Drawing no. | Sheet | Rev |
|---|---|---|
| **DWU-DC-E-SLD-002** | **2 / 2** | **P2** |