Design Basis: Electrical Concept

Nordic Hyperscale Data Center Campus · 30 MW IT · fictional site, bidding zone SE3, Sweden

Item	Value
Document	DWU-DC-E-DB-001, **Rev P2** (concept). Supersedes Rev P1 of 2026-10-24
Author	Donglin (Franklin) Wu, portfolio project 01
Date	2026-10-25
Status	Concept, **not for construction**
Related drawings	DWU-DC-E-SLD-000 (legend & drawing list), -001 sh. 1–2 (130 kV substation, MSG-20), -002 sh. 1–2 (data hall DH-1), -003 sh. 1–2 (power block A), -004 (BESS plant). All are Rev P2
Related calculations	DWU-DC-E-CALC-002 (load & sizing), -CALC-003 (short circuit, protection, arc flash), -CALC-004 (BESS)

> **Disclaimer.** This is a self-initiated portfolio exercise. The site, the grid connection and all parameters are **fictional assumptions** chosen to be technically plausible. They are based only on public standards and general industry practice. No employer, client or vendor data has been used. Values marked **(A)** are assumptions. Values marked **[C2]**, **[C3]** or **[C4]** were confirmed or changed by calculation CALC-002, -003 or -004.

Revision history

Rev	Date	Description	By
P1	2026-10-24	First issue for the concept: design basis, first-pass ratings, SLD-001…003	D. Wu
P2	2026-10-25	Incorporates every rating change from CALC-002/003/004 (TODO_final_fixes §B rows 1–31). Redrawn SLD set: legend sheet, sheets split for ≥ 2.5 mm text on A3, IEC 60617 symbols for CT, VT, surge arrester, earthing switch, relays, meters and arc sensors, and a new BESS sheet SLD-004. Changes are listed in §12	D. Wu

---

1. Purpose and scope

This document fixes the design inputs for the electrical concept of a 30 MW (IT) hyperscale campus. It covers everything from the 130 kV grid connection down to the rack power supplies. It is the common foundation for the later portfolio projects:

Project	Content	Uses from this basis
01 (this)	Design basis + concept single-line diagrams	—
02	Load calculation & equipment sizing tool (Python/Streamlit), CALC-002	Load model §5, ratings §8
03	IEC 60909 short-circuit, protection coordination & arc flash, CALC-003	Network data §7–8, Table 8.1
04	BESS: peak shaving, backup role, markets, AI-load smoothing, CALC-004	Grid data §3, 20 kV BESS bays §7.5

Out of scope at this stage: * detailed mechanical design and physical layout (beyond the BESS spacing rule in §7.5) * cable routing * detailed earthing-grid design (open point in §11) * the commercial grid-connection process

2. Design objectives

1. **Availability:** meet **EN 50600 Availability Class 3**, which means concurrently maintainable power distribution. Also target the equivalent of **Uptime Institute Tier III**. In addition, no single component failure in the IT power chain may drop IT load. This is fault tolerance beyond Tier III. The **BESS is not counted** towards this capacity (§7.5).

2. **Efficiency:** * **Annualised PUE ≤ 1.17** (restated in P2). CALC-002 computes **1.165** at 75 % IT utilisation with Dalarna temperature bins and the P1 equipment. * The P1 target of ≤ 1.15 is kept only as a **stretch target**. Reaching it needs one of the following:
    - mechanical pPUE **≤ 0.035 in free-cooling hours**, from EC fans, higher CHW/TCS temperatures and pump turndown, instead of the 0.05 assumed
    - UPS ESS/eco mode (η ≈ 99 %) for at least ≈ 60 % of the hours
    - **Design-peak PUE ≈ 1.26** at +32 °C [C2].
3. **Modularity:** build in 3 phases of 10 MW IT. Every data hall uses repeatable prefabricated 2.5 MVA "power blocks".
4. **Grid friendliness:** * Stay within the **40 MW subscription**, including after a grid outage when the UPS batteries recharge (§5.2, §7.5). * Provide a 10 MW / 20 MWh BESS for peak shaving and for Svenska kraftnät frequency services (FCR-N / FCR-D / mFRR) [C4]. * Large synchronous AI-training loads must respect a ramp limit agreed with the DSO (§7.6).
5. **Sustainability:** run gensets on **HVO100** renewable diesel. Allow for heat recovery to the local district-heating network (fjärrvärme).

3. Site assumptions (A)

Item	Assumption
Location	Fictional greenfield plot, Dalarna County, Sweden. Electricity bidding zone **SE3**
Altitude	≈ 150 m a.s.l. (no derating of equipment needed)
Climate (design)	Annual mean ≈ +4.5 °C. Winter design −28 °C. Summer design 0.4 % dry bulb ≈ +27 °C. Extreme design for heat rejection **+32 °C**. Gensets and dry coolers rated for **−30 … +35 °C**
Free cooling	Indirect free cooling (dry coolers / water-side economiser) available **> 95 % of hours** with a 27 °C supply-air envelope (ASHRAE A1 recommended)
Grid	Two **independent 130 kV lines** from two regional DSO substations ("Nord", "Syd") on separate routes. Svenska kraftnät 400 kV backbone upstream
Grid strength at 130 kV	S″k max **3 000 MVA**, min **1 500 MVA**, X/R ≈ 10. If S″k is above about 4 000 MVA, recheck the 20 kV peak current (§7.2) [C3]
Connection capacity	**40 MW** subscribed (abonnerad effekt), power factor at the connection point ≥ 0.95. EU Demand Connection Code (Reg. (EU) 2016/1388) requirements apply as specified by the DSO. **No export** assumed (BESS behind the meter)
Soil / seismic	Moraine, no seismic design requirement. Soil resistivity ≈ 500 Ω·m (to be measured)

4. IT load and phasing

Phase	Data halls	IT load	Cumulative	Notes
1	DH-1, DH-2	10 MW	10 MW	130/20 kV substation (both transformers) and MSG-20 built in full in Phase 1
2	DH-3, DH-4	10 MW	20 MW	BESS 10 MW / 20 MWh (two 5 MW units) can be added from Phase 2
3	DH-5, DH-6	10 MW	30 MW	
(4)	—	—	—	Spare 20 kV bays for expansion

- Each data hall: **5.0 MW IT**, about 200 racks at an average of 25 kW. The design allows up to 4 rows of liquid-cooled AI racks at 80–130 kW per rack, fed through CDUs.
- Racks are **dual-corded**, with two PSUs per server that share load and can each take the full load (standard hyperscale / OCP practice).
- The design IT load is the nameplate allocation. Average utilisation for energy estimates: **75 %** (A).

5. Load estimate and PUE (updated to CALC-002)

5.1 Per data hall, design peak (+32 °C ambient)

Load	P1 (MW)	P2 (MW) [C2]	Basis (A)
IT (critical)	5.00	**5.00**	Allocation
UPS losses	0.21	**0.18**	Efficiency curve at 62.5 % load, η ≈ 96.6 %
Mechanical (dry-cooler fans, trim chillers, pumps, fan walls, CDUs)	0.85	**0.85**	Mechanical pPUE 0.17 at +32 °C
Transformer and distribution losses	0.08	**0.07**	≈ 1.2 % of the downstream load
House services (lighting, BMS, security, UPS-room HVAC)	0.10	**0.10**	
Hall total (excl. battery recharge)	6.24	**6.20**	**pPUE ≈ 1.24**
Battery recharge (non-coincident, sizing only)	+0.80	**+0.80**	10 % of 4 × 2.0 MW
Hall maximum for MV feeder sizing	≈ 7.0 MW	**7.00 MW, 7.37 MVA**	**213 A** at 20 kV (feeder 390 A, OK)

5.2 Campus

Item	Value
Campus design-peak demand (6 halls + 0.5 MW services + HV transformer losses)	**37.8 MW / 39.8 MVA** at +32 °C → **design-peak PUE 1.26** [C2]
Campus maximum including non-coincident UPS recharge after a grid outage	**42.6 MW**. This is **above the 40 MW subscription** [C4]. See the rule below
Annualised PUE (75 % IT, Dalarna temperature bins)	**1.165 computed; target ≤ 1.17** (stretch 1.15, §2)
Annual energy estimate	197 GWh IT, **≈ 230 GWh facility** per year

Recharge rule (new in P2, TODO B26): after the grid returns, UPS battery recharge is **staggered by the EPMS and limited to ≤ 2.2 MW in total for the campus**, unless the BESS is available to cover the difference. While on gensets, recharge is limited to 5 % per block (§7.3). The rule keeps the import at or below 40 MW on the design day, and the design must not depend on the BESS for it.

6. Redundancy concept

6.1 Comparison of UPS / power-train architectures

The table compares the options for one 5 MW data hall. Scores are qualitative, and the CAPEX figures are rough ratios against 2N, based on public industry literature.

Criterion	2N (A/B fully duplicated)	N+1 (parallel-redundant modules, single bus)	Distributed redundant (4N/3)	Block redundant (4+1 "catcher")
Installed UPS/gen capacity vs. load	200 %	≈ 125 % (N = 4)	**133 %**	125 %
Electrical CAPEX (relative)	100 % (highest)	≈ 60–65 %	**≈ 75–80 %**	≈ 75 %
Footprint	Largest	Smallest	**Medium**	Medium
Concurrent maintainability (Tier III / Class 3)	Yes	**No** (single distribution path)	**Yes**	Yes
Single-fault tolerance of distribution	Yes (Tier IV capable)	No	**Yes** (any one block)	Yes, but relies on transfer (STS / bypass) to the reserve
Normal UPS loading → efficiency	≤ 50 % → lowest efficiency	≈ 80 % → best	**62.5–75 % → good**	Primaries ≈ 80–100 %, reserve idle → good
Complexity / operational risk	Simple, intuitive	Simple, but the bus is a single point of failure	Rack-pair allocation and load discipline (DCIM) required	Reserve bus and transfer coordination. A fault on the reserve bus can affect every block
Scalability in phases	Pairs of systems	Module by module	**Block by block (good)**	Needs the reserve block early

6.2 Chosen architecture: distributed redundant 4N/3 + 2N mechanical

- Each data hall has **4 identical IT power blocks A–D**, each made up of 20/0.42 kV transformer, genset, MSB, UPS and UOSB. Any **3 blocks carry the full 5 MW**.
- Every rack is dual-corded across a **unique pair of blocks** (pair-groups AB, AC, AD, BC, BD, CD, ≈ 0.83 MW each).
- Normal block load is **1.25 MW**.
- After losing any one block, each surviving block carries **1.67 MW**, which is **83 %** of its 2.0 MW UPS rating.
- **Mechanical loads** get **2N** boards (MSB-M1 / M2, each 100 %). Fans, CDUs and pumps are on a **mechanical UPS** for continuous cooling.
- **MV level:** dual-radial 20 kV feeders A and B to each hall, each rated for the full hall load. Hall MV board in two sections with a normally-open coupler.
- **HV level:** two 130 kV lines and two 63 MVA transformers. Each line/transformer pair carries the **whole campus** (N+1).
- **BESS:** not part of the redundancy concept. Gensets and UPS are sized without it (§7.5).

Why this choice:

1. It achieves Tier III / Class 3 concurrent maintainability **and** single-fault tolerance for about 20–25 % less electrical plant than 2N.
2. There is no STS or "catcher" reserve bus in the critical path, so there is no shared component whose failure can affect all blocks. Dual-corded IT makes the pairing native.
3. The block is a standard 2.5 MVA prefabricated skid (eHouse + genset). That suits phased hyperscale deployment and repeatable procurement.
4. UPS units run at 62.5 % normally, which is in the high-efficiency region of modern modular UPS. ECO / ESS mode can be considered.
5. **Accepted trade-off:** load placement must keep each block ≤ 1.67 MW in any N-1 case. EPMS/DCIM monitors this, and the allocation rule is part of the operating procedures.

7. Electrical system description

7.1 Voltage levels and system earthing

Level	Use	System earthing
130 kV	Grid connection (DSO)	Per DSO practice (YN winding provided, neutral earthing per DSO)
20 kV (24 kV equipment)	Campus distribution	**Resonant (compensated) earthing, confirmed in P2** [C3]. See below
400/230 V, 50 Hz	LV distribution, UPS, IT	**TN-S** per SS 436 40 00. 4-pole switching at source transfer, single N-PE bond (central earthing point, CEP) per switchboard
110 V DC	Substation protection and control	2 × 100 % chargers + battery
24 V DC / 48 V DC	Controls / rack-level (OCP)	—

20 kV neutral earthing (TODO B21, B25). Each MSG-20 section has the following: * a ZNyn earthing transformer * an **automatically tuned Petersen coil of at least 50 A**, continuously adjustable, about 10–60 A * a **10 A parallel resistor**, switched in for selective earth-fault detection

Capacitive current: * **≈ 22 A per section**, rising to 44 A with the coupler closed. * The BESS cables and transformers add **≈ +1 A**. The BESS transformers have delta windings at 20 kV, so they add no zero-sequence path.

Detection uses admittance or transient directional earth-fault protection [67N/59N]. Low-resistance earthing at 500 A was evaluated in CALC-003 and rejected. Its arc energy and EPR are higher, and it gives no ride-through on cable faults.

7.2 130/20 kV customer substation (sheet SLD-001 sh. 1–2)

Arrangement and transformers * **H-arrangement**: line CB → bus section (normally-open bus-section CB) → transformer CB. * **T1, T2:** 63 MVA (40 MVA ONAN / 63 MVA ONAF), 130 ±9×1.67 % / 21 kV, YNd11, uk ≈ 12 %, on-load tap changer. P_k ≈ 250 kW. * Surge arresters are fitted at: * the 130 kV line entries * the transformer HV terminals * the transformer LV terminals and at every 20 kV cable termination

MSG-20 switchgear * 24 kV, 2 500 A, **25 kA / 3 s, Ip 62.5 kA**, IEC 62271-200, LSC2B-PM, IAC AFLR 25 kA 1 s, preferably SF_6-free. * Two sections with a normally-open coupler.

Short-circuit levels [C3]

Case	I″k	Peak ip	Against rating
Normal (S0, one transformer per section)	**13.0 kA**	34.4 kA	Ip 62.5 kA
Normal with BESS	**13.3 kA**	—	+0.38 kA inverter contribution at 1.2 × In [C4]
Worst abnormal case	22.7 kA, **23.1 kA with BESS**	—	92 % of 25 kA

Interlocks (TODO B12, B13) * **T1//T2 paralleling is interlocked out.** The bus coupler auto-closes only after the incomer of the lost transformer is proven open (break-before-make). With T1//T2 the peak would be ip 58.5 kA, which is 94 % of 62.5 kA, and above 100 % at S″k 4 000 MVA. The R-TX CT would also saturate. * **Hall-board coupler (HV-DH1 and similar):** it may close only when one of the two hall feeders is open. With both feeders and the coupler closed, T1 and T2 would be in parallel through the hall board (20.9 kA).

20 kV feeders per section: * 6 data-hall feeders (630 A VCB, 3×1×240 mm² Al cable, ≈ 0.6 km, 390 A capacity in ground) * an earthing transformer bay with the Petersen coil and resistor (§7.1) * a station-aux transformer (500 kVA) * **a BESS bay: 630 A, one per section** (§7.5) * a spare

Protection settings [C3] (TODO B19, B20)

Relay	CT	51 setting	50 setting
R-INC (20 kV incomer)	2 500/1 5P20 15 VA, + 0.2S metering core	Is 2 100 A, IEC SI, TMS 0.16	I≫ 6 000 A, 0.65 s
R-FDR (hall feeder)	**400/1 5P20 15 VA**	Is 320 A, IEC VI, TMS 0.84	I≫ 2 400 A, 0.35 s
R-TX (block transformer, at HV-DH1)	**150/1 5P20 10 VA, Ith ≥ 25 kA 1 s**	Is 100 A, IEC EI, TMS 1.0	I≫ 1 500 A, 0.05 s

- All MV grading margins are ≥ 0.30 s.
- **Busbar protection:** reverse-blocking (incomer 50 blocked by any outgoing-feeder start), on both MSG-20 and HV-DH1.
- **Optical arc protection** (light + current, [50ARC]) trips the section incomer and the coupler. This reduces the incident energy in MSG-20 and HV-DH1 from ≈ 106 to ≈ 11 cal/cm² (Lee method) [C3] (TODO B18).

7.3 Data hall distribution (sheet SLD-002 sh. 1–2)

Hall MV board and transformers * **Hall MV board HV-DH1:** 24 kV, 1 250 A, 25 kA / 1 s. * Section 1 feeds T-A, T-C and T-M1. Section 2 feeds T-B, T-D and T-M2. * Coupler interlock as in §7.2. * **IT block transformers:** 4 × 2 500 kVA cast resin, Dyn11, uk 6 %, **P_k ≈ 19 kW, P_0 ≈ 3.1 kW** (Ecodesign Tier 2 order). * P2 aligns the loss values with CALC-002/003; P1 had P_k ≈ 22 kW (TODO B9). * Loading 65 % normal, **82 % in N-1** [C2]. * **Mechanical transformers:** 2 × **1 600 kVA kept** (TODO B8). * The mechanical load is ≈ 1 030 kVA, so 1 250 kVA would pass at 83 %. * 1 600 kVA (65 %) is kept on purpose. It leaves ≈ 20 % margin for growth in liquid cooling (CDUs) and for starting the 400 kW trim chillers. It also gives a common spare with the 1 650 kVA mechanical gensets.

Gensets and transfer * **Gensets:** one per block, each with an ATS. * IT: 2 750 kVA / 2 200 kWe DCC, 88 % loaded in N-1. * Mechanical: 1 650 kVA / 1 320 kWe, governed by the 400 kW chiller step (≤ 33 %). * **Open transition in both directions only (TODO B14).** Closed-transition retransfer at the MSB is not permitted. With grid and genset in parallel, the MSB would see 81.8 kA / ip 187 kA, which is above the 65 / 143 kA rating [C3]. * The genset ACB uses short-delay pick-up **Isd ≤ 2.5 × Ir**. The genset specification requires a **sustained short-circuit current of at least 300 % for 2 s** (PMG or AREP excitation) so that the genset ACB and the downstream devices trip.

Fuel (TODO B6) * HVO100, **24 h** at design load on site (A; Tier III requires ≥ 12 h). * **≈ 51 m³ gross per hall** (46 m³ net, 90 % usable), in bulk and day tanks [C2]. * The volume includes the 5 % recharge allowance, the part-load SFC and the mechanical gensets.

7.4 Power block (sheet SLD-003 sh. 1–2)

Power path * MV feeder → T-A → MSB-A (4 000 A) → 2 × 1 000 kW UPS modules in parallel → UPS output bus → UOSB-A (3 200 A) → 6 × 800 A overhead busways (2 runs per pair-group) → 63 A 3P+N tap-offs → rack PDUs.

Connections and ratings * **T-A → MSB:** 4 000 A busbar trunking, ≈ 10 m. * **Genset → MSB generator incomer: 4 000 A busbar trunking** (≈ 40 m) (TODO B5). A cable would need 8 × 3×1×240 Cu. The alternative is to locate the genset room next to the MSB. * **MSB → SBS (static bypass) input: 3 200 A busbar trunking** (≈ 25 m) (TODO B4). A cable would need 7 × 3×1×240 Cu. * **MSB:** * 65 kA board. * **Icw 65 kA / 1 s, Ipk ≥ 143 kA** specified. * Computed fault levels: * I″k 52.3 kA, ip 122 kA with the cables and busduct modelled [C3] * 53.8 kA / ip 129 kA as a hand value at the transformer terminals [C2] (TODO B10) * **UPS rectifier input breakers: 2 000 A** (TODO B2). The maximum input current is 1 660 A at rated power plus 10 % recharge. The alternative is to limit grid recharge to ≤ 5 %. * **UPS battery: LFP, 165 kWh nameplate per 1 000 kW module** (TODO B1). * Governed by the C-rate: ≤ 8 C at end of life. 120 kWh would need 10.7 C. * Gives 5 min at the rated load at end of life, and 8.1 min at the N-1 load.

Critical distribution: short-circuit ratings (TODO B3, B15, B16)

Location	Fault level [C3]	Requirement
UOSB	49.3 kA	—
Busway start	37.1 kA	Busway Icw is 36 kA. Each busway is fed by a **current-limiting MCCB, Icu ≥ 50 kA**, with a **tested busway conditional short-circuit rating ≥ 40 kA** (IEC 61439-6)
Busway end (tap-off)	25.1 kA	**63 A MCCB Icu ≥ 36 kA**, or a tested cascade with the busway MCCB
Rack inlet	14.0 kA	**Rack PDU conditional SCCR ≥ 15 kA**

LV trip-unit settings (TODO B19)

Device	Ir	tr	Isd	tsd	Other
MSB incomer ACB	3 600 A	3 s	4 × Ir	0.3 s	—
SBS ACB	2 900 A	1 s	2.5 × Ir	0.2 s	—
Busway MCCB	800 A	—	4 × Ir	0.1 s	Ii 12 × Ir
Genset ACB	4 000 A	12 s	2.5 × Ir	0.4 s	—

Arc-flash mitigation on MSB and UOSB (TODO B17) * **Optical arc relays** with **intertrip of the 20 kV block-transformer VCB**. This covers the MSB line side, which the incomer cannot clear. * **ZSI** between the incomer and the outgoing ACBs. * An **arc-reduction maintenance switch (ARMS)** on each incomer. * Effect: the MSB line side falls from 96 to 3.2 cal/cm², and the bus from 16.8 to 2.4–4.8 cal/cm² (IEEE 1584-2018) [C3]. * Final labels are issued only after the vendor study.

Bypass and testing * **Centralised static bypass (SBS)** and an **external wrap-around maintenance bypass (MBB)**. The MBB is key-interlocked with the UPS output breaker. * Each MSB has a **load-bank connection** for commissioning and periodic genset testing.

7.5 Battery energy storage (sheet SLD-004) [C4]

Plant and connection (TODO B22, B23) * **10 MW / 20 MWh LFP** in two units of 5 MW / 10 MWh. * Each unit has its own **630 A CB bay**, one per MSG-20 section (Q19 and Q29), with these parts: * CT 200/1 5P20, plus a 0.2S revenue core * VT 20/√3 / 0.1/√3 kV, cl. 0.2/3P * surge arresters and an earthing switch * Unit rating 5.5 MVA, 159 A. * PCS transformers: 2 × 5.5 MVA, 20/0.69 kV, **Dyn (delta at 20 kV)**. * PCS: 4-quadrant, grid-following, with a grid-forming option. The **11 MVA** gives Q capability for the p.f. ≥ 0.95 at the connection point. * Revenue and aggregator metering: cl. 0.2S, separate from the EPMS.

Bay protection * 50/51, 50N/51N/67N * 27/59, 81U/O, 59N * loss of mains (ROCOF / vector shift) * **intertrip from R-INC**, so that the BESS trips when its section loses the grid * 25 synchro-check, only if the grid-forming mode is used

Role and limits * Peak shaving under 40 MW gives **+2.4 MW** extra IT capacity. The **firm** value at N-1 BESS is only **+0.84 MW**, and only that value may be sold as IT capacity. * The battery provides FCR-N, FCR-D up/down, mFRR and arbitrage. * **The BESS is not counted** as Tier III / EN 50600 Class 3 capacity (TODO B28). The gensets and UPS are unchanged, because the BESS has 27 min at campus peak against 24 h of fuel.

EMS / power-plant controller priorities (TODO B27) 1. Grid import limit of 40 MW, including recharge (§5.2). 2. SOC reserve before forecast peaks. 3. Reserve headroom for FCR down-activation. Down-activation counts against the import limit. 4. Markets.

If the BESS is unavailable, IT power capping is the fallback.

Island operation (not in the base design; TODO B28) * The 20 kV relays do **not** clear an island fault fed only by the inverters: 381 A at 20 kV, and R-FDR would take ≈ 60 s. * Bridging a genset fail-to-start would therefore need all of the following: * a grid-forming PCS * island protection: 51V, definite-time 27, or 87L * soft energisation * an open-position interlock on the 130 kV CB * an island earthing check

Power quality (TODO B29) * A harmonic study to IEC/TR 61000-3-6, with the DSO, of PCS plus UPS rectifiers, is an **open point** (§11).

Fire safety and layout (TODO B30) * Outdoor LFP containers, at least **10 m (A)** from halls, transformers and fuel tanks. * Container data to UL 9540A, design to NFPA 855, EN IEC 62485-5 and IEC 62933-5-2. * Explosion control to NFPA 68/69. * Early consultation with the Räddningstjänst (fire and rescue service).

7.6 Large AI-training loads (TODO B31)

Synchronous AI training can swing a hall by several MW within seconds.

Connection agreement * State a **grid ramp limit** in the connection agreement: 3 MW/min (A), agreed with the DSO. * State an oscillation limit in the 0.1–2 Hz band: ≤ 1 MW peak-to-peak (A).

What smoothing a 12 MW swing needs [C4] * ≈ 11.4 MW of BESS power, so the 10 MW BESS is marginal. The energy needed is below 0.5 MWh. * A response of **≤ ~10 ms** for the ripple. A BESS with a 150 ms response leaves 5.6 MW peak-to-peak.

Specified mitigation, one or a combination of: * a supercapacitor or hybrid stage (≈ 23 kWh per 10 MW) * UPS-level smoothing * a GPU-side power floor or ramp control in the workload scheduler

8. Equipment ratings (Rev P2)

Equipment	Qty (campus)	Rating (P2)	Sizing check / source	Change vs P1
130/20 kV transformer T1, T2	2	63 MVA ONAF, uk 12 %, YNd11, OLTC	N-1 63 % (ONAF) [C2]	—
20 kV main switchgear MSG-20	1 (2 sections)	2 500 A, 25 kA / 3 s, Ip 62.5 kA	13.0 kA normal, 13.3 kA with BESS, worst 23.1 kA [C3/C4]; section ≈ 1 150 A	values updated
Hall feeders	12	630 A VCB, CT 400/1, 3×1×240 Al	213 A ≤ 390 A [C2]	CT added
BESS bays	**2**	**630 A CB, CT 200/1, VT**	159 A per unit [C4]	**new**
Petersen coil + resistor	2	≥ 50 A adjustable + 10 A	Ic 22 A per section (44 A coupled), +1 A BESS [C3]	specified
IT block transformer	24	2 500 kVA, 20/0.42 kV, Dyn11, uk 6 %, Pk 19 kW	N-1 82 % [C2]	Pk aligned
Mechanical transformer	12	1 600 kVA, uk 6 %	65 % (1 250 kVA would be 83 %), margin kept	rationale
IT genset	24	2 750 kVA / 2 200 kWe DCC, sustained Isc ≥ 300 % for 2 s	N-1 88 % [C2]	spec added
Mechanical genset	12	1 650 kVA / 1 320 kWe	400 kW chiller step ≤ 33 % [C2]	—
Fuel per hall	6	**≈ 51 m³ gross** (24 h)	[C2]	38 → 51 m³
UPS (per block)	24 × 2 modules	2 × 1 000 kW, VFI-SS-111	N-1 83 %	—
UPS rectifier input breaker	48	**2 000 A**	1 660 A max [C2]	1 600 → 2 000 A
Battery (per module)	48	**LFP 165 kWh nameplate**	C-rate ≤ 8 C at EoL; 5 min at Pr, 8.1 min at N-1 [C2]	120 → 165 kWh
MSB (IT block)	24	4 000 A, **Icw 65 kA / 1 s, Ipk 143 kA**, Form 4b, optical arc relays + MV intertrip, ZSI, ARMS	52.3 kA / ip 122 kA [C3]	spec added
Genset → MSB / MSB → SBS	24 + 24	**4 000 A / 3 200 A busbar trunking**	[C2]	cable → BTS
UOSB	24	3 200 A, 65 kA / 1 s, optical arc relays	49.3 kA [C3]	arc protection
Busway feeder MCCB	144	**Current-limiting, Icu ≥ 50 kA, tested conditional ≥ 40 kA**	busway start 37.1 kA > Icw 36 kA [C3]	specified
Busway	144	800 A, Icw 36 kA	survivor 614 A at 40 °C [C2]	—
Tap-off devices / rack PDU	—	**63 A MCCB Icu ≥ 36 kA or tested cascade; PDU SCCR ≥ 15 kA**	25.1 / 14.0 kA [C3]	specified
Mechanical UPS	12	2 × 250 kW, 10 min	Fans, CDUs, CHW pumps	—
BESS	1 (2 units)	**10 MW / 20 MWh LFP, PCS 2 × 5.5 MVA, Dyn 20/0.69 kV**	[C4]	**new**

8.1 Network data (as used in CALC-003)

Element	Data
130 kV grid	S″k max/min 3 000 / 1 500 MVA, c_max = 1.10, R/X = 0.1
T1/T2	63 MVA, 130/21 kV, uk = 12 %, P_k ≈ 250 kW, YNd11
20 kV cables	3×1×240 Al: R ≈ 0.125 Ω/km, X ≈ 0.11 Ω/km, ≈ 0.6 km per feeder. 3×1×95 Al to transformers ≈ 0.15 km
T-A … T-D	2.5 MVA, 20/0.42 kV, uk = 6 %, **P_k ≈ 19 kW**, Dyn11
IT genset	2 750 kVA, x″d ≈ 15 %, x′d ≈ 22 %, R/X ≈ 0.15
BESS PCS	2 × 5 MW, fault current 1.2 × In (A, generic), response ≈ 150 ms (A)
Results [C3]	**20 kV: 13.0 kA** (P1 hand estimate ≈ 14 kA). **MSB-A: 52.3 kA** full model, 53.8 kA at the transformer terminals (P1 ≈ 52 kA). IEC 60909 with K_T. The pandapower cross-check gives the same result in the max case

9. Protection and control philosophy (concept)

- **130 kV:** line differential / distance [87L/21], transformer differential [87T], restricted earth fault [64REF], Buchholz [63], oil/winding temperature [26/49], breaker failure [50BF]. Coordinated with the DSO.
- **20 kV:**
- Feeder overcurrent [50/51] and earth fault [50N/51N].
- Directional earth fault [67N] for resonant earthing (admittance or transient method).
- Reverse-blocking busbar protection and optical arc protection [50ARC].
- Incomer/coupler automatic transfer, break-before-make, with lock-out on bus fault.
- BESS bay protection as in §7.5.
- Settings are in §7.2.
- **LV:**
- LSI(G) electronic trip units (settings in §7.4), with ZSI between the incomer and the outgoing ACBs.
- MCB/MCCB pairs are current-selective only up to ≈ 8.6 kA. Above that, the manufacturer's selectivity tables are required (open point).
- Arc-flash mitigation as in §7.4.
- **Monitoring:** EPMS with class 0.5S meters on every incomer and outgoing (PUE per EN 50600-4-2), and 0.2S revenue meters at the 20 kV incomers and the BESS. IEC 61850 at MV/HV, Modbus TCP at LV. Integration with DCIM/BMS.

10. Applicable standards and regulations

Area	Reference
Swedish regulation	**ELSÄK-FS 2022:1** (Elsäkerhetsverket: how high-voltage/“starkström” installations shall be designed). Elsäkerhetslagen (2016:732). Elsäkerhetsförordningen (2017:218)
LV installations	**SS 436 40 00** (Swedish implementation of IEC/HD 60364), **IEC 60364** series
HV installations	SS-EN 61936-1 (installations > 1 kV AC), SS-EN 50522 (earthing > 1 kV)
LV switchgear / busway	**IEC 61439-1/-2** (switchboards), **IEC 61439-6** (busbar trunking), IEC 60947-2 (breakers)
MV/HV switchgear	**IEC 62271-1/-100/-200**
Transformers	IEC 60076 series, IEC 60076-5 (short-circuit withstand), IEC 60076-11 (dry type)
UPS	**IEC 62040-1/-3**
Batteries / BESS	IEC 62619, EN IEC 62485-5, IEC 62933-5-2, UL 9540A (test data), NFPA 855
Gensets	ISO 8528 series
Short-circuit / arc flash	**IEC 60909-0**, IEEE 1584-2018
Protection	IEC 60255 series (IEC 60255-151 curves). IEC 61850 (communication)
Instrument transformers	IEC 61869-2 (CT), IEC 61869-3 (VT)
Surge protection	IEC 60099-4 (MV/HV arresters), IEC 61643-11 (LV SPD), IEC 62305 (lightning)
Graphical symbols	IEC 60617 (SLD symbols), IEEE C37.2 (device numbers), ISO 3098 / ISO 5457 (lettering, sheet format)
Data centres	**EN 50600-1, -2-2 (power distribution), -4-2 (PUE)**. Uptime Institute Tier Standard: Topology (reference)
Grid connection	Regulation (EU) 2016/1388 (Demand Connection Code), DSO technical requirements, Svenska kraftnät rules for FCR/mFRR (BESS prequalification)

11. Key assumptions and open points

1. Grid capacity and connection timeline are assumed available. In reality, grid capacity is the critical-path item for Nordic data centres.
2. **130 kV substation earthing:** this needs a detailed study with DSO data (soil model, EN 50522). The 130 kV earth-fault EPR of ≈ 800 V exceeds 2·UTp at 0.5 s back-up clearing [C3]. This is **open**.
3. Assumed data must be confirmed with the DSO and vendors: * grid S″k of 1 500–3 000 MVA (above 4 000 MVA the 20 kV peak margin is lost) * UPS inverter current limit * PDU rating * cable capacitance * earth resistance * PCS fault-current curve (1.2 pu assumed)
4. Generic LV device curves must be replaced with the selected manufacturer's curves and selectivity/cascade tables. Arc-flash labels are issued only after the final study with vendor clearing times.
5. **BESS:** confirm with the DSO whether FCR activation or export is allowed under the 40 MW subscription. Also check Svk FCR/mFRR prequalification, aggregator terms and market depth. The CALC-004 revenue is an upper bound.
6. A **harmonic and reactive-power study** of the UPS rectifiers, VFDs and BESS PCS, to IEC 61000-3-12, IEC/TR 61000-3-6 and the DSO limits. Long 20 kV cables at light load generate capacitive reactive power. The BESS PCS can absorb it.
7. Rack density growth (AI/liquid cooling) can raise hall IT load above 5 MW. The block approach allows a 5th block per hall if the space is reserved.
8. Heat recovery to district heating (heat pumps ≈ 2–4 MW extra electrical load) is not included in the base load. It would also count against the 40 MW subscription.

12. Changes in Rev P2 (traceability to TODO_final_fixes.md)

TODO	Change	Section
A1–A3	SLD set redrawn: ≥ 2.5 mm text on A3, IEC 60617 symbols, legend sheet SLD-000, sheets split, new SLD-004	Drawings
B1, B2	Battery 165 kWh per module; rectifier input breaker 2 000 A	§7.4, §8
B3, B15, B16	Busway MCCB and tap-off device ratings; PDU SCCR	§7.4, §8
B4, B5	Busbar trunking for MSB → SBS (3 200 A) and genset → MSB (4 000 A)	§7.4, §8
B6	Fuel 51 m³ per hall	§7.3, §8
B7	Annual PUE target ≤ 1.17 (stretch 1.15 with conditions)	§2, §5.2
B8	Mechanical transformer 1 600 kVA kept, with rationale	§7.3
B9	Block transformer Pk 19 kW	§7.3, §8.1
B10, B11	I″k 52.3/53.8 kA (MSB) and 13.0 kA (20 kV); Icw/Ipk	§7.2, §7.4, §8.1
B12, B13	T1//T2 and hall-coupler interlocks	§7.2
B14	Open-transition-only retransfer; genset sustained Isc	§7.3
B17, B18	Arc-flash mitigation at LV and MV	§7.2, §7.4
B19, B20	Trip settings, relay settings, CT ratios	§7.2, §7.4
B21, B25	Petersen coil + resistor specification; Ic +1 A	§7.1
B22–B24	BESS bays, BESS single-line, I″k with BESS	§7.2, §7.5, SLD-004
B26	Recharge rule under 40 MW	§5.2
B27	EMS priorities; firm IT +0.84 MW	§7.5
B28	BESS not counted in Tier III; island protection note	§7.5
B29	Harmonic study open point; Q capability	§7.5, §11
B30	BESS spacing and fire codes	§7.5
B31	AI ramp clause	§7.6
C	Open points carried into §11. These are not resolved, because they need DSO or vendor data	§11

Appendix A: Concept SLD sheets, Rev P2 (reduced previews; the vector originals are in `drawings/`).

SYMBOL LEGEND (IEC 60617 forms)


Circuit breaker


Circuit breaker, withdrawable


Disconnector


Switch-disconnector

Fuse



Earthing switch


Current transformer (2 cores)


Voltage transformer


Surge arrester / SPD


Busbar (weight per level)


Transformer, 2 windings

Earth



Generator, 3-phase


Rectifier (ac/dc), inverter (dc/ac)


Static bypass switch


Battery


Adjustable inductor (Petersen coil)

Resistor

Busbar trunking / busway



Energy meter (Wh)



Protection relay, device no.

Optical arc sensor

Interlock (mechanical / key)

Protection / control signal


Off-sheet connector

LINE CODE (black on white; no colour code)

130 kV conductor	20 kV conductor	0.4 / 0.69 kV conductor
130 kV busbar	20 kV busbar	0.4 / 0.69 kV busbar
UPS / critical busbar	protection / control	interlock

Voltage level is also stated on every busbar tag; genset and BESS circuits use the LV weight.

UPS COMPOUND SYMBOL (all sheets)



rectifier ac/dc (top), inverter dc/ac (bottom),
DC link with battery to the side;
drawn the same for IT UPS and mechanical UPS.

DRAWING LIST (Rev P2)

Drawing / sheet	Title
SLD-000	Legend, drawing list, notes
SLD-001 sh 1	130/20 kV substation
SLD-001 sh 2	20 kV main switchgear MSG-20
SLD-002 sh 1	Data hall DH-1: HV-DH1, blocks
SLD-002 sh 2	DH-1: UPS, busways, mechanical
SLD-003 sh 1	Power block A: T-A, G-A, MSB-A
SLD-003 sh 2	Power block A: UPS to rack
SLD-004	BESS plant 10 MW / 20 MWh

ABBREVIATIONS

ACB / VCB air / vacuum circuit breaker
ATS automatic transfer (open transition)
ARMS arc-reduction maintenance switch
BTS busbar trunking system
MSB / UOSB main / UPS output switchboard
SBS / MBB static / maintenance bypass
PCS / EMS power conversion / energy mgmt
ZSI zone-selective interlocking
LoM loss of mains (ROCOF / vector shift)
(A) assumed value

GENERAL NOTES


1. Concept drawings for a fictional campus; not for construction. Public standards, [ASSUMED] data.
2. Ratings per DB-001 Rev P2 and CALC-002/003/004.
3. Relay functions: IEEE C37.2 device numbers.
4. Minimum text 10 pt = 2.57 mm cap height at A3 (checked by scripts/check_drawings.py).

P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

Legend, drawing list, notes
Symbols to IEC 60617 · lettering to ISO 3098
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-000	**1 / 1**	**P2**



SUBSTATION NOTES

1. Each line + transformer carries the whole campus (N+1): 37.8 MW design peak, 42.6 MW with UPS recharge.
2. Q-HBC closes only with one line out.
3. T1 // T2 via MSG-20 is interlocked out (IL-1 on sh 2, TODO B12).
4. Arresters at the line entries and at the HV and LV terminals of T1/T2.
5. Protection supply 110 V DC, 2 × 100 % chargers + battery.
6. Relay functions IEEE C37.2; settings and CT data per CALC-003.
7. 130 kV earthing study is an open point (DSO data, EN 50522).


Short-circuit level (CALC-003/004)	Value
130 kV S''k max / min (A)	3 000 / 1 500 MVA
20 kV normal (S0)	13.0 kA, ip 34.4 kA
20 kV with BESS	13.3 kA
Worst abnormal + BESS	23.1 kA = 92 % of 25
T1 // T2 (not permitted)	ip 58.5 kA = 94 %

P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

130/20 kV substation — sheet 1
H-arrangement, T1/T2 to the MSG-20 incomers
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-001	**1 / 2**	**P2**




FEEDER SCHEDULE (relay settings per CALC-003)

Bay	Feeds	Device	CT	Protection / metering
Q10 / Q20	T1 / T2 incomer	VCB 2 500 A wd	2500/1 5P20 + 0.2S	51 SI 2 100 A TMS 0.16 50 6 000 A 0.65 s
Q11–16 / Q21–26	DH-1…6 feed A / B	VCB 630 A wd	400/1 5P20 15 VA	51 VI 320 A TMS 0.84 50 2 400 A 0.35 s
Q17 / Q27	ESG: ZNyn + coil	VCB 630 A wd	200/1 5P20	50/51, 51N, 59N
Q18 / Q28	Aux 500 kVA	VCB 630 A wd	100/1 5P20	50/51, 50N/51N
Q19 / Q29	BESS-1 / -2 5.5 MVA	CB 630 A wd	200/1 5P20 + 0.2S	see SLD-004
Q1A / Q2A	spare, equipped	VCB 630 A wd	400/1 5P20	as feeders
Q-BC	coupler (N.O.)	VCB 2 500 A wd	2500/1 5P20	50/51, IL-1

NOTES

1 Resonant (compensated) earthing kept; 500 A low-resistance earthing rejected (CALC-003).
2 All feeders: 67N admittance earth-fault relays.
3 Reverse-blocking busbar protection + optical arc protection (50ARC, light + current) trips the section incomer and Q-BC (TODO B18).
4 Hall-board coupler closes only with one hall feeder open (IL-2, SLD-002 sh 1).
5 Every bay: SA 24 kV at the cable end, ES, EPMS 0.5S.
6 DH feeders A → HV-DH1 S1, B → S2 (SLD-002).
7 ESG-1/2: detail B. AUX: 500 kVA station aux.
8 BESS bays Q19 / Q29 → SLD-004 (TODO B22).

DETAIL B earthing bay Q17 / Q27




P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

20 kV main switchgear MSG-20 — sheet 2
2 sections, coupler, earthing bays, BESS bays
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-001	**2 / 2**	**P2**



ATS (dash-dot): transformer ACB / genset ACB, open transition only (TODO B14). Gensets via BTS 4 000 A (B5).


Item	Rating (Rev P2)	Check (CALC-002/3)
T-A…T-D	2 500 kVA 20/0.42 kV Dyn11, uk 6 %, Pk 19 kW	N-1 82 %
G-A…G-D	2 750 kVA / 2 200 kWe DCC, Isc ≥ 300 % 2 s	N-1 88 %
MSB-A…D	4 000 A, Icw 65 kA 1 s, Ipk 143 kA	52.3 kA
UPS-A…D	2 × 1 000 kW, 2 × 165 kWh LFP	N-1 83 %
UOSB-A…D	3 200 A, 65 kA 1 s	49.3 kA
T-M1/M2	1 600 kVA kept (1 250 kVA would be 83 %)	65 %
G-M / MUPS	1 650 kVA; mech. UPS 2 × 250 kW	step ≤ 33 %

P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

Data hall DH-1 — sheet 1
HV-DH1, IT power blocks A–D (4N/3), mechanical 2N
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-002	**1 / 2**	**P2**



4N/3 ALLOCATION

Pair-group	Busways (block 1)	Busways (block 2)	IT load
AB	BW-A1, BW-A2	BW-B1, BW-B2	0.83 MW
AC	BW-A3, BW-A4	BW-C1, BW-C2	0.83 MW
AD	BW-A5, BW-A6	BW-D1, BW-D2	0.83 MW
BC	BW-B3, BW-B4	BW-C3, BW-C4	0.83 MW
BD	BW-B5, BW-B6	BW-D3, BW-D4	0.83 MW
CD	BW-C5, BW-C6	BW-D5, BW-D6	0.83 MW

Each rack is dual-corded to the two blocks of one pair-group (2 busway runs per block).

LOADING (CALC-002)

Case	Block load	UPS	Busway
Normal	1.25 MW	63 %	307 A
Loss of 1 block	1.67 MW	83 %	614 A
DCIM limit	≤ 1.67 MW	—	Ir 800 A

NOTES


1. UOSB 3 200 A, Icw 65 kA 1 s; SPD type 2.
2. Busway MCCB 800 A current-limiting, Icu ≥ 50 kA, tested conditional rating ≥ 40 kA (IEC 61439-6).
3. Busway 800 A, Icw 36 kA; tap-off 63 A MCCB Icu ≥ 36 kA; rack PDU SCCR ≥ 15 kA (CALC-003).
4. Battery per UPS module LFP 165 kWh (5 min).
5. Block A detail: SLD-003 sh 1–2.

P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

Data hall DH-1 — sheet 2
UPS, UOSB, busways to 4N/3 pair-groups; mechanical 2N
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-002	**2 / 2**	**P2**



LV TRIP SETTINGS (CALC-003)

Device	Ir	tr	Isd	tsd	Other
Q-UI incomer	3 600 A	3 s	4 × Ir	0.3 s	ZSI, ARMS
Q-SB (SBS)	2 900 A	1 s	2.5 × Ir	0.2 s	ZSI
Q-GI genset	4 000 A	12 s	2.5 × Ir	0.4 s	—
Busway MCCB	800 A	—	4 × Ir	0.1 s	Ii 12 × Ir

NOTES


1. ATS: break-before-make, no closed transition (closed: 81.8 kA / ip 187 kA > MSB rating).
2. ZSI Q-UI ↔ outgoing ACBs; ARMS on Q-UI.
3. Arc energy MSB line side 96 → 3.2 cal/cm², bus 16.8 → 2.4–4.8 cal/cm² (IEEE 1584).
4. Ratings are [ASSUMED] concept values.

P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

Power block A — sheet 1
20 kV feeder, T-A, genset G-A, MSB-A (typical of 24)
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-003	**1 / 2**	**P2**



EQUIPMENT SCHEDULE

Item	Rating (Rev P2)	Basis
UPS-A1/A2	1 000 kW each, VFI-SS-111	N-1 83 %
Battery	LFP 165 kWh per module, ≤ 8 C EoL	B1
Rectifier breaker	Q-R1/Q-R2 2 000 A (1 660 A max)	B2
SBS / MBB	3 200 A, BTS 3 200 A from MSB	B4
Busway MCCB	800 A, Icu ≥ 50 kA, cond. ≥ 40 kA	B3, B15
Tap-off / PDU	63 A Icu ≥ 36 kA; SCCR ≥ 15 kA	B16

NOTES

1. Fault levels in boxes: I″k per CALC-003.
2. SBS is centralised per block; MBB is external wrap-around (IL-4).
3. A2…A6 identical to BW-A1; pairing per SLD-002 sh 2.


P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

Power block A — sheet 2
UPS-A1/A2, SBS, MBB, UOSB-A, busway to rack (typical)
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-003	**2 / 2**	**P2**

SLD-003-2_block_A_UPS_critical



EMS / PPC priorities

1. Import ≤ 40 MW incl. recharge
2. SOC reserve before peaks
3. FCR down headroom
4. Markets (FCR, mFRR)

Fallback: IT power capping → R-B1, R-B2, PCS-1/2

BESS SCHEDULE

Item	Rating (Rev P2)	Note
Bays Q19 / Q29	VCB 630 A, CT 200/1 5P20 + 0.2S	unit 159 A at 20 kV
TR-B1 / TR-B2	5.5 MVA 20/0.69 kV Dyn	delta at 20 kV
PCS-1 / PCS-2	5.5 MVA each, 11 MVA total	p.f. ≥ 0.95 at PCC
BESS-1 / BESS-2	5 MW / 10 MWh LFP each	10 MW / 20 MWh
I″k contribution	≤ 1.2 × In (PCS limit), 13.0 → 13.3 kA	CALC-004

NOTES

1. Not counted as Tier III / EN 50600 Class 3 capacity; firm IT gain +0.84 MW (peak shaving +2.4 MW).
2. No island operation in the base design: 20 kV relays do not clear an inverter-fed island fault (381 A, R-FDR ≈ 60 s).
3. Containers ≥ 10 m (A) from halls, transformers, fuel; UL 9540A, NFPA 855, IEC 62933-5-2.
4. Harmonic study (IEC/TR 61000-3-6) open.

P2	2026-10-25	CALC-002/3/4 ratings, IEC symbols, ≥2.5 mm text
P1	2026-10-24	First concept issue

Nordic Hyperscale DC Campus (fictional) · 30 MW IT · SE3
Portfolio D. Wu · public standards and [ASSUMED] data only

BESS plant — 10 MW / 20 MWh
2 units, MSG-20 bays Q19 / Q29, protection and EMS
CONCEPT · NOT FOR CONSTRUCTION · scale NTS · A3

Drawing no.	Sheet	Rev
DWU-DC-E-SLD-004	**1 / 1**	**P2**